



Association of
Professional
Energy Managers



OR APEM 2016 Fall Forum
RCx Stories from the Field

Josh Weissert, PE
September 23, 2016

- Commissioning is:
 - An extremely important, but costly, time consuming endeavor
 - Includes functional testing of every device
 - Typically done on new construction or major renovation projects
 - Should be done on all mechanical system upgrades
- Retrocommissioning:
 - Can be full point to point commissioning of existing building, but most people aren't willing to pay for that
 - More exploratory
 - Leverages control systems as a window into mechanical systems

- Know your stuff! – Your job is to find opportunities that building managers, HVAC contractors and control contractors missed
- Question Everything!
- Approach interactions with humility
 - Remember that you're being critical of someone's baby (facility managers spend a lot of time with the systems you're looking for flaws in)
 - You might learn something (if your mind is open to it)
- Need to be specific in measure identification and SOW to implement
 - A contractor needs to price your recommended fix
 - A contractor needs to implement it in a way that achieves the desired energy savings
- The details matter! Without careful oversight of RCx implementation, the building may not save any energy!
- Oversee contractors carefully! Give them punch lists!
- Make sure contractor payment is tied to approval by you as the RCx agent


RCx Stories from the Field





- Energy Star Building
- Has implemented a number of capital projects, even LED lighting
- All electric, water cooled DX, VAV airside systems
- Through Retrocommissioning, saved 16% of energy use (794,386 kWh)
- Energy Star score went from 80 to 91
- Project included minimal capital equipment
- Savings have been measured and verified at the meter
- Building manager billed the expense to the triple net – means the tenants paid for it!

1000 Broadway Results (CUSUM)



LEED Buildings aren't Necessarily Efficient!



- Newer LEED Gold Building
- EUI 69 kBtu/sft
- 14% savings potential for \$15,000 in RCx measures




Heat Pump RCx on E350's Office

Baseline SW Heat Pump




Post RCx SW Heat Pump






- We rarely agree that a project is done when a contractor or customer says it's done
- Usually when a project is first considered complete, they're missing 10-100% of the anticipated energy savings
- The incremental savings that comes from the final commissioning phase are the most cost effective savings available.

Chiller Performance vs Cond Temp



What's Wrong with This?



Optimum Start

Set how you want to calculate optimum start for this zone. Select None to disable optimum start. Standard

Standard

Self-tuning Factor 0=disable, 0.1=least aggressive, 1.0=most

Outside Air Limit

Building Mass 3=light, 4=medium, 5=heavy

Warmup Factor

Cooldown Factor


Humidity Value

Use different factors when previous day has no scheduled occupancy.
To enable, set both Warmup and Cooldown factor to one (1). To disable, set one of Warmup or Cooldown factor to NULL.


Alternate Warmup Factor

Alternate Cooldown

Scheduling Example Continued



Operator Overrides are Extremely Inefficient




Leaking Valves




- We rarely see leaking valves when looking at them.

Leaking Valves



Central Plant RCx – Wet Bulb Approach Tower Control



What is it and What's Wrong?




What is it and What's Wrong?



Broken Economizers

- Very common issue in both commercial and industrial facilities.

What is it and What's Wrong?



What is it and What's Wrong?




Refrigerant Condenser Pressure Switch
Never Connected

What is it and What's Wrong?



What is it and What's Wrong?





Industrial Refrigeration

- TXV Calibration
- Incrementally Raise Suction Pressure Setpoint
- Compressor Sequencing
- Together, these eliminated the need for a compressor

This was at our verification for newly installed steam traps!



The Tough Reality of RCx

Measures are subtle and tough to identify



More on 1000 Broadway

- Reduce scheduled occupied times (including exhaust fans)
 - Exhaust Fans run 4:00AM-7:00PM Mon-Fri, 8:00AM-Noon Sat - Should adjust schedule to match AHUS.
 - AHUS run 6:00AM-7:00PM Mon-Fri, 8:00AM-Noon Sat - Can we make this 7AM - 6PM? They actually go into occupied mode at 6:00, but with smart sleep, they're coming on at 9:00 at least in this colder weather.
 - Can we shorten the lighting schedule?
- Enable morning warmup
 - Command OA Dampers fully closed during morning warmup if DAT<50
 - SAT reset
 - SP reset
- Fix broken economizers - Suspect economizers include:
 - AC9 - Seems to have very high minimum OA
 - AC10 - Compressor runs in cold weather
 - AC18 - Compressor runs in cold weather
 - AC21 - Compressor runs in cold weather
 - AC23 - Compressor runs in cold weather

- Fix broken VAV dampers
 - VAV 0625 Zone 23
 - VAV 1024 Zone 46
 - VAV 1116 Zone 15
 - VAV 1502 Zone 12
 - VAV 1326 Zone 10
 - VAV 1514 Zone 14
 - VAV 1528 Zone 17
 - VAV 2020 Zone 49
- Is R 15 zone 23 temperature sensor working right? We're cooking it heavily and it says it's 77.
- Reduce Lobby & Theater OA
 - Optimize CW Loop
 - Isolate the cooling tower bypass on the primary condenser water loop.
 - Reduce primary flow through R6 - On this until we get a similar OT on each side of the heat exchanger. We could also just measure flow on each side and balance primary flow to match secondary. We should leave the primary a little more than the secondary for when the lobby & theater units need cooling.
 - Program CW pumps to sequence up and down. I think there's plenty of time when we only need one of those.
 - Reduce primary CW OP setpoint from 17 PSI to 7777
 - Program the secondary pumps to lead with the good one and bring the other one on once a week for an hour to exercise it. Also make sure it's programmed so that if the lead fails, the other comes on as a backup.
- Look to Reduce Lighting Schedule - RR and hall lights run 6AM-midnight and from midnight-7AM
- AC 18 economizer linkage needs to be connected to the actuator.
- What controls BA exhaust fans? They were running at 1:00 PM on Saturday.
- What's TF-17? It runs every day from 7AM-7PM

We should do a lighting sweep at 8:00 PM then bring the hallway lights back on.

They don't clean Fri & we can shut lighting off at

| | | | |
|------------------------------|------------------|--------------------------|-------------------------|
| VAV Name: | VAV-1024 Zone 46 | VAV 1 | Parallel Fan, with Heat |
| Active Mode: | Occupied | | |
| Present Value: | Occupied | Override | |
| Space Temperature: | 72 Deg | | |
| Unoccupied Cooling Setpoint: | 65 Deg | Active Cooling Setpoint: | 74 Deg |
| Occupied Cooling Setpoint: | 74 Deg | Active Heating Setpoint: | 72 Deg |
| Unoccupied Heating Setpoint: | 72 Deg | Heat Actuator: | Yes |
| | | Parallel Fan Output: | On |



| | |
|-----------------------------|---------|
| Air Valve Position: | 25.00 % |
| Air Valve Flow: | 196 CFM |
| Air Valve Control Actuator: | Cooling |

- I reprogrammed the min CFM to 60.

- why does the air valve not close more?

- why does the air valve stay cooling mode, yet fan & heat are on?

| Economizers | SP | Actual |
|-------------|----|--------|
| -AC9 | 51 | 67 |
| -AC10 | | |
| -AC11 | | |

up to AC 18 AC 12 → 10% AC 13 → 10%

| | SP | Actual |
|-------|----|--------|
| AC 11 | 67 | 67 |

| | | |
|-------|----|----|
| AC 13 | 67 | 51 |
| AC 14 | 67 | 64 |

| | | |
|-------|----|--|
| AC 15 | 67 | 62 → still low |
| AC 18 | 67 | 53 → linkage is disconnected from actuator |

| | | |
|-------|-----|----|
| AC 20 | 116 | 60 |
| AC 21 | 67 | 61 |

| | | |
|-------|----|----|
| AC 22 | 67 | 53 |
| AC 23 | 67 | 54 |

AC 16 working?
AC 12 working?


AC 22 @ 10%

* Bathroom exhaust fans are on sat at 1:00 what controls them?


* What's EPI? It runs every day 7AM-7PM

* Need to fix


More on 1000 Broadway




More on 1000 Broadway



It's in optimal start mode & programmed for a morning warmup temp of 70. Why ~~is it~~ is the SAT SP 55? This is making it hard to warm up the building.



Can we isolate this?
Need to sequence these.
One should suffice most of the time.



| Conditions of Service | | | | Motor Data | | |
|-----------------------|------|-------------|----|------------|-----|--|
| Flow | Temp | Suct. Press | HP | Voltage | Eff | |
| Flow | Temp | Dis. Press | HP | 1750 | Eff | |
| Flow | Temp | Dis. Press | HP | 1750 | Eff | |

| Flow | Temp | Eff | HP |
|-------|------|-----|------|
| 725 | 54 | 97% | 14.0 |
| 500 | 100 | 58% | 21.3 |
| 750 | 125 | 71% | 71.7 |
| 1,000 | 155 | 80% | 42.1 |

Lessons Learned – RCx is a great opportunity – but tough!

- Finding RCx opportunities is tough!
- While most customers are open to RCx, it's too complex for them to undertake themselves.
- If you hand a customer an RCx study and end your engagement there, implementation rates will be low.
- Successful RCx requires a high level of assistance and expertise – To identify opportunities, but also through the implementation & verification phases.
- RCx needs to be Commissioned! – Contractors rarely get it right the first time! The details matter! QC is critical to achieving savings!

Closing Thought – Assume Nothing – Question Everything!





Questions?

Josh Weissert

josh@energy350.com

503-830-6075